

## British Steel, Lackenby Collection Plan

Loading:

Monday - Friday 0600-1800 **POST CODE: TS10** 

5QW


**PPE Requirements:** 







## Reporting/Arrival:










**LACKENBY MAIN ENTRANCE** 

**INDUCTION PRAIRIE 4 OFFICE** 

**LOADING PRAIRIE** 

## Loading/Securing:

Stand in **GREEN** area during loading





**MIN X 13** 



**Max X 65** 

Straps LC 2500 daN










Apply partial load restraint then transit to strapping area near Prairie Office to apply straps and edge protection. NO CLIMBING USE PLATFORM PROVIDED!

- 3. Overview of restraint system
- ✓ Pyramid load build see Section 4.
- ✓ Over-the-top webbing straps see Table 1 or Table 2.
- ✓ Ratchets placed on alternating sides.
- ✓ Straps can be attached to the chassis if there is insufficient



(road, ferry and rail). Number of straps required.



	Load	LC 2000 daN		LC 2500 daN		LC 5000 daNl	
	15-20 t	11		9		5	
	20-25 t	14		11		6	
	25-28 t	16		13		7	

This Load Restraint Guideline is designed to be compliant with the forces stated in EN 12195-1:2010 and VDI 2700.