

British Steel, Skinningrove Ponderosa FN Billets Flatbeds

Loading:

Monday - Friday 0700-1900

POST CODE: TS13 4ET

PPE Requirements:



Additional Information:









Reporting/Arrival:



ON ARRIVAL STOP AT **SECURITY GATE IN PPE**



DRIVER RECEPTION / INDUCTION



MIN X 12 MIN X 8





WEIGHBRIDGE Weigh ON

Use a platform to place minimum 3 stanchions and 3 timbers strapped down to create false headboard **NO CLIMBING**




Collect 6 x Large Timbers and 8 X Anti-slip Mats



Set Timbers and ASM as per LRG and then go to Safe Haven



Stand in **SAFE HAVEN** during loading. Only leave when loader gives permission DOORS MUST BE KEPT CLOSED WHEN



loading



00 7 00

Straps MIN LC 2000 daN













NOT WORN









LOADS MUST BE SECURED IN THE STRAPPING AREA - PLEASE HAVE ALL EQUIPMENT READY SECURING INFORMATION ON REVERSE SIDE

TAD 0117 FN Billet 3 AXLE TRACTOR UNIT

ALL Collections MUST be with 3 Axle Tractor Units to achieve full loads OF 26.5Tonnes.

2. Essential requirements

- · All loads must be blocked in the forwards direction.
- · All restraints must be a minimum of LC 2000 daN webbing straps and must be compliant with EN 12195-2.
- Webbing sleeve edge protection must be fitted to webbing straps in contact with the product and the chassis frame (unless otherwise stated).
- Anti-slip matting must be placed between all base timbers and the trailer deck.
- Loads must be placed in accordance with TIS-0012 Axle loads and weight distribution.
 - ✓ Stanchions must be a minimum of 80mm x 80mm with a wall thickness of 5mm Steel Grade S355.

